

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

MAY 1 1975  
5-1-75  
CONSERVATION DIVISION  
Wichita, Kansas  
15-151-20253-0000

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Kansas-Nebraska Natural Gas Co. Inc. & Sterling Drlg Co

Complete Address Box 129 Sterling, KS

Lease Name Smith Well No. 1

Location NW/NW Sec. 21 Twp. 26 Rge. 15 (E) (W) W

County Pratt Total Depth 4450

Abandoned Oil Well        Gas Well X Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Sterling Drlg Co

Address Box 129 Sterling KS License No.       

Operation Completed: Hour 2:00 PM Day 29 Month 4 Year 1975

The above well was plugged as follows:

422 ft 8 5/8 surface cemented with 350 sacks. 2464 ft 2 7/8" tubing

cemented with 225 sacks. Top perf. 2336 ft. Pump sand & 3 sacks

cement to 2300 ft. Pulled 1877 ft 2 7/8" tubing. Pump 3 sacks hulls,

10 sacks gel, 100 sacks cement to surface.

Pumped by Halliburton Cementing Great Bend, KS

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]  
Well Plugging Supervisor

DATE 5/1/75

INV. NO. 1256-W