

R

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
11 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Pratt County. Sec. 21 Twp. 26S Rge. 15 (W)

NORTH

Locate well correctly on above
Section Plat

Location as "NE/CNW/SW" or footage from lines: SE NW SW
 Lease Owner: Bowers Drilling Company, Inc.
 Lease Name: Smith Well No.: 1
 Office Address: 1434 Wichita Plaza, Wichita, Kansas
 Character of Well (completed as Oil, Gas or Dry Hole): Dry Hole
 Date well completed: August 1 19 64
 Application for plugging filed: August 5 19 64
 Application for plugging approved: August 1 19 64
 Plugging commenced: August 1 19 64
 Plugging completed: August 1 19 64
 Reason for abandonment of well or producing formation: Dry Hole

If a producing well is abandoned, date of last production: 19
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes, verbally

Name of Conservation Agent who supervised plugging of this well
 Producing formation: Depth to top: Bottom: Total Depth of Well: 4240 Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	454	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled with heavy mud to 300'
 Set first plug at 300' with 25 sacks

Filled with heavy mud to 40'
 Set second plug at 40' with 10 sacks
 cement, 1/4 sack hulls, 3 sacks in
 rathole

RECEIVED
 STATE CORPORATION COMMISSION

AUG 6 1964

CONSERVATION DIVISION
 Wichita, Kansas

8-6-64

(If additional description is necessary, use BACK of this sheet)
 Name of Plugging Contractor: Bowers Drilling Company, Inc.
 Address: 1434 Wichita Plaza, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
 Emil E. Bowers, (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Emil E. Bowers
 1434 Wichita Plaza, Wichita, Kansas
 (Address)

SUBSCRIBED AND SWORN TO before me this 5th day of August, 19 64

My commission expires May 1, 1966

Notary Public.

WELL LOG

R

COMPANY: Bowers Drilling Company, Inc.
 CONTRACTOR: Bowers Drilling Company, Inc.
 FARM: Smith #1
 LOCATION: SE NW SW Section 21-26S-15W
 Pratt County, Kansas
 COMMENCED: July 24, 1964
 COMPLETED: August 1, 1964
 ELEVATION: 2061 K.B.

0 - 274 Sand
 274 - 454 Sand and Redbed
 454 - 957 Redbed
 957 - 1908 Redbed, shale and shells
 1908 - 2596 Lime and shale
 2596 - 3128 Shale
 3128 - 3875 Lime and shale
 3875 - 3918 Shale
 3918 - 4240 Lime
 4240 T. D.

RECEIVED
STATE CORPORATION COMMISSION

AUG 6 1964

CONSERVATION DIVISION
Wichita, Kansas

SAMPLE TOPS:

Heebner	3763	Douglas Sand	3841
Toronto	3778	Brown Lime	3917
Douglas Shale	3802	Lansing	3936

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I, Emil E. Bowers, doe hereby certify that the above and foregoing is a true and correct copy of the copy of the log of the Smith #1 located SE NW SW Section 21-26S-15W, Pratt County, Kansas, as reflected by the files of Bowers Drilling Company, Inc.

Emil E. Bowers

Subscribed and sworn to before me, a Notary Public in and for Sedgwick County, Kansas, this 5th day of August, 1964.

Donna F. Miller, Notary Public

My commission expires May 1, 1966.