


15-51-26098-0000

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
11 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Pratt County, Sec. 30 Twp. 26S Rge. 15 (XX) (W)



Locate well correctly on above Section Plat

Location as "NE/CNWSW4" or footage from lines: NE SW NE
 Lease Owner: Bowers Drilling Company, Inc.
 Lease Name: Tatlock Well No. 1
 Office Address: 1434 Wichita Plaza, Wichita, Kansas
 Character of Well (completed as Oil, Gas or Dry Hole): Dry Hole
 Date well completed: November 7 19 68
 Application for plugging filed: November 14 19 68
 Application for plugging approved: November 7 19 68
 Plugging commenced: November 7 19 68
 Plugging completed: November 7 19 68
 Reason for abandonment of well or producing formation: Dry Hole

If a producing well is abandoned, date of last production: 19
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes, verbally

Name of Conservation Agent who supervised plugging of this well: _____
 Producing formation: _____ Depth to top: _____ Bottom: _____ Total Depth of Well: 4438 Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	365	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled with heavy mud to 360'
 Set first plug at 360' w/ 1/2 sack hulls and 25 sacks cement
 Filled with heavy mud to 40'
 Set second plug at 40' with 1/2 sack hulls, 10 sacks cement

RECEIVED
 STATE CORPORATION COMMISSION
 NOV 18 1968
 CONSERVATION DIVISION
 Wichita, Kansas

11-18-68

(If additional description is necessary, use BACK of this sheet)
 Name of Plugging Contractor: Bowers Drilling Company, Inc.
 Address: 1434 Wichita Plaza, Wichita, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK, ss.
Emil E. Bowers (employee-of-owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Emil E. Bowers
1434 Wichita Plaza, Wichita, Kansas
 (Address)

SUBSCRIBED AND SWORN TO before me this 14th day of November 19 68
Sherry Gish
 Sherry Gish Notary Public.

My commission expires 6-30-71

WELL LOG

15-151-20098-0006

COMPANY: Bowers Drilling Company, Inc.
 CONTRACTOR: Bowers Drilling Company, Inc.
 FARM: #1 Tatlock
 LOCATION: NE SW NE Section 30-26S-15W
 Pratt County, Kansas
 COMMENCED: October 29, 1968
 COMPLETED: November 7, 1968
 ELEVATION: 2071 Kelly Bushing

0 - 175	Sand and clay
175 - 580	Shale and clay
580 - 1000	Redbed
1000 - 1599	Shale
1599 - 2155	Shale and shells
2155 - 3962	Lime and shale
3962 - 4438	Lime
4438	T. D.

SAMPLE TOPS:

Langdon Zone	3061 (-990)
Topeka	3357 (-1286)
Heebner	3756 (-1685)
Toronto	3778 (-1707)
Douglas	3795 (-1724)
Brown Lime	3913 (-1842)
Lansing/Kansas City	3927 (-1856)
Base/Kansas City	4256 (-2185)
Kinderhook	4364 (-2293)
Viola	4424 (-2355)
RTD	4438 (-2367)


RECEIVED
 STATE CORPORATION COMMISSION
 NOV 18 1968
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I, Emil E. Bowers, do hereby certify that the above and foregoing is a true and correct copy of the log of the #1 Tatlock located NE SW NE Section 30-26S-15W, Pratt County, Kansas, as reflected by the files of Bowers Drilling Company, Inc.


 Emil E. Bowers, President

Subscribed and sworn to before me, a Notary Public, in and for the State of Kansas this 14th day of November, 1968.


 Sherry Gish, Notary Public

My commission expires June 30, 1971