

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Pratt County, Sec. 30 Twp. 26 Rge. 15 (E) (W)

Location as "NE/CNW/SW" or footage from lines NE SE NW

Lease Owner Mull Drilling Co., Inc.

Lease Name Tatlock Well No. B-1

Office Address 670 North Suite Fourth National Bank Bldg. Wichita

Character of Well (completed as Oil, Gas or Dry Hole) Dry hole

Date well completed 5-24-58 19

Application for plugging filed 5-24-58 19

Application for plugging approved 5-24-58 19

Plugging commenced 9:00 A. M. 5-24-58 19

Plugging completed 11:00 A. M. 5-24-58 19

Reason for abandonment of well or producing formation No oil or gas production


If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Broad Foot

Producing formation Dry Hole Depth to top Bottom Total Depth of Well 4686 Feet

Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above Section Plat

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Well was plugged with 30 sacks of common cement, #1 plug @ 200' with 1/2 sack hulls on top, and 20 sacks cement mixed by dump method. Hole then was filled with heavy mud to within 40' of top, of hole. #2 plug pushed to 40' 1/2 sack hulls put on top of #2 plug, and 10 sacks cement then dumped on top of plug. Job completed.

STATE CORPORATION COMMISSION
Wichita, Kansas

5-29-58

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Company tools

Address

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Joseph O. Butts (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Joseph O. Butts

(Address)

SUBSCRIBED AND SWORN to before me this 28th day of May, 19 58

Ethel Zimmerman
Ethel Zimmerman Notary Public.

My commission expires January 28, 1961

PLUGGING
FILE SEC 30 T 26 R 15 W
BOOK PAGE 103 LINE 40

15151-00049-0000

ROTARY DRILLERS LOG

COMPANY: Mull Drilling Co., Inc. Et Al
Wichita, Kansas

ROTARY DRILLING COMMENCED: 5/9/58

CONTRACTOR: Mull Drilling Co., Inc.
Wichita, Kansas

ROTARY DRILLING COMPLETED: 5/24/58

CASING RECORD: 8 5/8" @ 777' w/525 sax cnt.

LOCATION: TATLOCK "B" #1
NE SE NW Sec. 30-26-15W
Pratt, County, Kansas

(Figures indicate bottom of formation - measurements from top of Rotary Bushing)

1150'	Blue Shale & Red Bed
1475'	Shale, etc.
1995'	Shale & Shells
3155'	Lime & Shale
3356'	Sandy Lime
3378'	Lime
3483'	Lime w/Shale
3783'	Lime
3902'	Sandy Lime
3912'	Brown Lime
3990'	Lansing Lime
4005'	Lansing Lime w/Shale
4078'	Kansas City Lime
4382'	Lime
4421'	Conglomerate, Lime & Chert
4510'	Viola Lime w/chert
4612'	Lime
4665'	Simpson Shale & Sand
4686'	Arbuckle T. D.

D. & A.


I hereby certify that this is true and correct copy of the above log to the best of my knowledge.

MULL DRILLING COMPANY, INC.

J. A. Mull, Jr.
J. A. MULL, JR.

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Subscribed and sworn to before me this 6th day of June, 1958.



My Commission Expires: February 24, 1960.

Madge D. Miller
Notary Public

PLUGGING
FILE SEC 30 T 26 R 15W
BOOK PAGE 103 LINE 40

RECEIVED
CORPORATION COMMISSION

JUN 7 1958
CONSERVATION DIVISION
Wichita, Kansas