


WELL PLUGGING RECORD

15-151-00093-0000

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

Pratt County, Sec. 30 Twp. 26S Rge. 15 (E) (W) X  
Location as "NE/CNWSW" or footage from lines SW SW SE  
Lease Owner Mull Drilling Company, Inc.  
Lease Name Chitwood Well No. 1  
Office Address 1625 Wichita Plaza Building Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole)  
Date well completed 19  
Application for plugging filed 3-7-67 19  
Application for plugging approved 3-2-67 19  
Plugging commenced 3-10-67 19  
Plugging completed 3-29-67 19  
Reason for abandonment of well or producing formation



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie V. Elving  
Producing formation Depth to top Bottom Total Depth of Well PB 4468 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	500	None
				5 1/2	None	3757

RECEIVED  
STATE CORPORATION COMMISSION

APR 7 1967

4-7-67

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Killing gas.  
Cleaning out cellar.  
Sanded to 4400'. Dumped 5 sacks of cement. Working pipe. Shot pipe at 3900' and 3800'.  
Working pipe. Pulled 5 joints of pipe.  
Working pipe. Circulating. Spotted 75 bbl of oil by Globe Cementing.  
Pulling pipe. Plugging well. Set rock bridge at 4400'. Dumped 25 sacks of cement. Filled hole and rock bridge. Capped well with 10 sacks of cement.

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Forbes Casing Pulling, Inc.  
Address P. O. Box 221 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
J. O. Forbes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *J. O. Forbes*  
P. O. Box 221 Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 6 day of April, 1967

*Glenn Baker*  
Notary Public.

My commission expires May 27, 1969

15-151-00053-0060

ROTARY DRILLERS LOG

COMPANY: Mull Drilling Co., Inc. Et Al  
Wichita, Kansas

ROTARY DRILLING COMMENCED:  
2-22-58

CONTRACTOR: Mull Drilling Co., Inc.  
Wichita, Kansas

ROTARY DRILLING COMPLETED:  
3-11-58

CASING RECORD: 862' of 8 5/8"  
cemented w/150 sax cement  
4578' of 5 1/2" csg.  
cemented with 150 saxs

LOCATION: Chitwood #1  
SW SW SE 30-26S-15W  
Pratt County, Kansas

(Figures indicate bottom of formation - measurements from top of Rotary Bushing)

850'	Sand & Red Bed
1290'	Anhydrite Shells & Shale
1600'	Shale
2940'	Shale & Lime
3200'	Sandy Lime & Shale
3391'	Sand & Lime
3524'	Lime & Shale
3665'	Lime
3772'	Sand & Lime
3887'	Sandy Lime & Shale
3947'	Shale & Lime
4230'	Lime
4344'	Lime w/Shale
4376'	Lime
4390'	Kinderhook Sand
4421'	Kinderhook Sand; Lime & Shale
4530'	Lime & Chert
4578'	Viola Lime & Chert T.D.

I hereby certify that this is true and correct copy of the above log to the best of my knowledge.

MULL DRILLING COMPANY, INC.

by Joseph B. Brungardt, Jr.  
Joseph B. Brungardt, Jr., Asst. Treas.

STATE OF KANSAS )  
                          ) SS  
COUNTY OF SEDGWICK)

Subscribed and sworn to before me this 2nd day of April, 1958.

Madge M. Miller  
Notary Public



My Commission Expires: February 24, 1960