

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-047-21179-0000

LEASE NAME R.G. Fouse

WELL NUMBER #4

500' FSL

SPOT LOCATION 20' FWL

NW 1/4

SEC. 1 TWP. 26 RGE. 16 (E) or (W)

COUNTY Edwards

Date Well Completed \_\_\_\_\_

Plugging Commenced 5-23-88

Plugging Completed 5-24-88

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR LITTLE GUY OIL & GAS, INC.

ADDRESS P.O. Box 8561 Pratt, Kansas 67124

PHONE # 16 ) 672-2030 OPERATORS LICENSE NO. 3454

Character of Well Oil  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City, Kansas

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom T.D. 4572'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		0		400'	8 5/8	none
		400'	4571'	5 1/2	4171	3709 1/2'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Bottom hole plug. Sand to 4290' plus 5 sx. cement on top. of sand.  
Plugging: 400# hulls, 10 sx. gel, 50 sx. cement, 10 sx. gel, 100# hulls, plug, 125 sx. cement. 40-60- perz. mix, 6 % gel. 450# max. pressure, 150# shut in pressure.  
Top hole: Added redi-mix to within 4' of top of ground level.

(If additional description is necessary, use BACK of this form.)

6-3-88

Name of Plugging Contractor Pratt Well Service, Inc.

License No. 5893

Address Box 847 Pratt, Kansas 67124

RECEIVED  
STATE CORPORATION COMMISSION

STATE OF Kansas

COUNTY OF Pratt


JUN - 3 1988

R.G. Howe

(operator) of above-described well, being first duly sworn on oath, say that I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R.G. Howe

(Address) PRATT, KANSAS



SUBSCRIBED AND SWORN TO before me this 27 day of May, 1988

Julia Berry  
Notary Public

My Commission expires: Feb. 6, 1989