

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15,047-21,163-0000

LEASE NAME R.G. Fouse

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER 2 west

330' Ft. from ~~XX~~Section Line

1 Ft. from E Section Line

SEC. W/4TWP.26S RGE.16W (~~XX~~or(W))

COUNTY Edwards

LEASE OPERATOR Little Guy Oil & Gas Corp.

ADDRESS P.O. Box 8561 Pratt, Kansas 67124

PHONE#(316) 672-2030 OPERATORS LICENSE NO. 3454

Date Well Completed Spud date 3-9-84

Character of Well Oil

Plugging Commenced _____

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 9-21-88

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City, Kansas

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4607

Show depth and thickness of all water, oil and gas formations. Perfs: 4527-30:4367-82: 4046-50: Plug, 4200': CIPB 4030; then perfs at 3991-95'.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | From | To | Size | Put in | Pulled out |
|-----------|------|------|-------|----------------------|------------|
| | 0 | 420 | 8-5/8 | 420' | 0 |
| | 420 | 4590 | 5 1/2 | 4170 4607 | 1476' |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Dumped 150 gallons of sand, 5 sx. cement, sanded back to 3890', shot off at 2470, 2068, 1831, 1476, and recovered 37 jts.

9-21-88: 4 hulls, 10 gel, 50 sx. cement, 10 gel, 1 hulls, plug, 125 sx. cement. 60 40 poz. 6% gel. FILLED WITH PEDI MIX ON 9-26-88.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Pratt Well Service, Inc. License No. 5893

Address P.O. Box 847 Pratt, Kansas 67124

STATE OF Kansas COUNTY OF Pratt, ss.


Judy Berry

(Employee of ~~Operator~~ plugging contractor) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Judy Berry

(Address) Box 847 - Pratt, Ks.



SUBSCRIBED AND SWORN TO before me this 7th day of October, 19 88

Dorothy M. Ferguson
 Notary Public

My Commission Expires: Feb 6, 1989