

15.047-20357-0000

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Edwards SEC. 1 TWP. 26S RGE. 16W E/W
 Location as in quarters or footage from lines:
C NW SE

Locate Well
 correctly on above
 Section Platt.

Lease Owner Beren Corporation
 Lease Name Bisel #1 Well No. _____
 Office Address 970 Fourth Financial Center Wichita, Ks. 67202
 Character of Well (Completed as Oil, Gas or Dry Hole): _____
 Date Well Completed _____
 Application for plugging filed _____
 Plugging commenced 3-14-83
 Plugging completed 3-16-83
 Reason for abandonment of well or producing formation _____

Depleted
 Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Steve Durrant
 Producing formation _____ Depth to top _____ bottom T.D. 4470'
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	401'	none
				4-1/2"	4467'	2420'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Pumped bottom with 25 sacks cement to 4300', shot casing @3427, 3028', 2826', 2627', 2423' and pulled a total of 59 joints of 4-1/2" casing. Plugged well with 3 hulls, 15 gel, 70 cement, 1 hull, 10 gel, released plug and displaced with 100 sacks cement, 50/50 pos, 4% gel, 3% cc.

Plugging Complete.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling
 R. _____

STATE OF Kansas COUNTY OF Rice, ss.
R. Darrell Kelso (employee of owner) or (owner or operator) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Box 347 Chase, Ks. 67524
 (Address)

SUBSCRIBED AND SWORN TO before me this 18th day of March, 19 83

Irene Hoover
 Notary Public.

My Commission expires: _____



RECEIVED
 STATE CORPORATION COMMISSION
3-21-83
 MAR 21 1983
 CONSERVATION DIVISION
 Wichita, Kansas

KANSAS DRILLERS LOG


API No. 15 — 097 — 20357-0000
 County Number

S. 1 T. 26S R. 16W E
 W

Loc. C NW SE

County Edwards.

640 Acres
 N



Elev.: Gr. _____

DF _____ KB 2050

Operator
Beren Corporation

Address
970 Fourth Financial Center, Wichita, Kansas 67202

Well No. 1 Lease Name BISEL

Footage Location
 feet from (N) (S) line _____ feet from (E) (W) line _____

Principal Contractor Murfin Drilling Geologist _____

Spud Date March 29, 1978 Total Depth 4470 P.B.T.D. _____

Date Completed April 11, 1978 Oil Purchaser _____

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4	8-5/8		401	60-40 pozmix	325	2% gel, 3% CC
Production		4 1/2		4467	" "	200	18% salt, 10# G/I

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production _____ Producing method (flowing, pumping, gas lift, etc.) _____

RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio
	bbls.	MCF	bbls.	CFPB

Disposition of gas (vented, used on lease or sold) _____ Producing interval (s) _____

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator

Beren Corporation

DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:

Well No.

1

Lease Name

BISEL

T A

S 1 T 26S R 16W E W

WELL LOG

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Sand	0	841		
Shale	841	2220		
Shale and lime	2220	2600		
Lime and shale	2600	3254		
Lime	3254	3375		
Lime and shale	3375	3520		
Lime, shale, chalk	3520	3646		
Lime	3646	3689		
Lime and shale	3689	3799		
Lime and chalk	3799	3910		
Lime	3910	4375		
Shale and lime	4375	4415		
Lime	4415	4470		
T.D.	4470			

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

Don Beauchamp

Signature

Don Beauchamp - Geologist

Title

February 2, 1979

Date