

Yp
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

NOV 2 1964
11-2-64
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Texaco Inc.

Complete Address: 614 Bitting Bldg., Wichita, Kansas

Lease Name A. C. Bowker Well No. # 3

Location SW SE SE Sec. 2 Twp. 25 Rge. 14 (E) (W)

County Stafford Total Depth 4185

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Comstock Pipe Pulling Inc.

Address: Stafford, Kansas License No. 490

Operation Completed: Hour 4:00PM Day 30th Month Oct. Year 1964

The Above well was plugged as follows:

883' of 10 3/4" surface pipe, cemented with 550 sacks. 4184' of 7" long
string, cemented with 100 sacks. Plug back to 4166'. Top perforation
3766'. Bottom plug was pushed to 3725', and 20' of sand bridge, and
cemented with 5 sacks. Hole was filled with mud to 275', and 15' of
rock bridge, and cemented with 30 sacks. Hole was filled with mud to
40', and 10' of rock bridge, and cemented with 15 sacks to the base
of the cellar.

2114' of 7" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 11/2/64

INV. NO. 94-W