

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

AUG 13 1963

8-13-63
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Western Petroleum Co. Inc.

Complete Address: Box 524, Great Bend, Kansas

Lease Name Wilson Well No. # 1

Location SW SW SW Sec. 5 Twp. 25 Rge. 14 (E) (W) W

County Stafford Total Depth 4445

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: This hole had been washed down

Plugging Contractor: Forbes Casing Pulling Co.

Address: Box 221, Great Bend, Kansas License No. 49

Operation Completed: Hour 9:00AM Day 12th Month August Year 1963

The Above well was plugged as follows:

304' of 10 3/4" surface pipe, cement circulated. 4320' of 5 1/2" long string,
cemented with 225 sacks. Top perferation 4171'. Pushed plug to 4153', rock
bridge, cemented with 5 sacks. Hole was flowing with water and a squeeze
job was necessary. 20 sacks of gel mud and 120 sacks of cement was pumped
into the surface pipe, through a 10 3/4" swage, at a pressure of 250 lbs.
This cementing was done by Globe Cementing Co.
2432' of 5 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 8/13/63
INV. NO. 9573-W

Signed: Archie Elving
Well Plugging Supervisor