

~~20~~
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

15-51-10915-0000

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
FEB 7 1964
2-7-64
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Morgenstern & Spector Inc.

Complete Address: Box 661, Russell, Kansas

Lease Name Elliot Well No. # 1

Location SE SE SW Sec. 21 Twp. 26 Rge. 15 (E) (W) W

County Pratt Total Depth 4710

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Lynch Casing Pulling Co.

Address: Route 4, Great Bend, Kansas License No. 457

Operation Completed: Hour 2:00PM Day 6th Month Feb. Year 1964

The Above well was plugged as follows:

272' of 8 5/8" surface pipe, cemented with 225 sacks. 4233' of 5 1/2" long
string, cemented with 200 sacks. Top perforation 3907'. Bottom of hole
was sanded to 3890', and cemented with 5 sacks. Fluid was up in hole.
Plug was set at 260', with 10' rock bridge. 6 sacks of cement was mixed
in barrel and put on plug through dump bailer, and let set over night.
Next morning hole bailed down, and 19 sacks of cement was added to the
plug. Hole was filled with mud to 40', 10' rock bridge, and cemented
with 10 sacks to base cellar. 3104' of 5 1/2" long string was recovered
from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 2/7/64

INV. NO. 8600-w