

Jp
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
MAY 25 1964
5-25-64
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Strata Drilling Inc. 15-151-19125-0000

Complete Address: P. O. Box 355, Great Bend, Kansas

Lease Name Tatlock Well No. # 1

Location NE NW SE Sec. 27 Twp. 26 Rge. 15 (E) (W) W

County Pratt Total Depth 4468

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Strata Drilling Inc.

Address: 2421 Tenth St., Great Bend, Kansas License No.

Operation Completed: Hour 1:00AM Day 24th Month May Year 1964

The Above well was plugged as follows:

328' of 10 3/4" surface pipe, cemented with 350 sacks. Fluid level was
up in the hole. 1st cementing plug and 1/2 sack hulls was pushed through
fluid to 275', and cemented with 35 sacks, through the drill pipe. Hole
was filled with drilling mud to 40', 2nd cementing plug, bridged solid
with hulls, and cemented with 15 sacks. Rat and mouse hole bridged and
cemented with 4 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 5/26/64
INV. NO. 9215-W