

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Well Plugging Authority,
issued March 2, 1967.

15-151-66053-0000

Operator's Full Name Mull Drilling Company, Inc.

Complete Address: 1625 Wichita Plaza Bldg., Wichita, Kansas

Lease Name Chitwood Well No. # 1

Location SW SW SE Sec. 30 Twp. 26 Rge. 15 (E) (W) W

County Pratt Total Depth 4509'

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Forbes Casing Pulling, Inc.

Address: Box 221, Great Bend, Kansas License No. 49

Operation Completed: Hour 5:00PM Day 29th Month March Year 1967

The Above well was plugged as follows:

500' of 8 5/8" surface pipe, cemented with 350 sacks. 4509' of 5 1/2" long
string, cemented with 125 sacks. Plug back T.D. 4468'. Top perferation
4409'. Bottom of the hole was sanded to 4400', and cemented with 5 sacks
through the dump bailer. 3750' of 5 1/2" long string was recovered from the
hole. Fluid level in the hole was at 400', bridge plug and rock bridge
from 400' to 390', and cemented with 25 sacks. Hole was filled with mud
to 40', rock bridge from 40' to 30', and cemented with 10 sacks to the
base of the cellar.

RECEIVED

I hereby certify that the above well was plugged as herein stated.

INVOICED

MAR 31 1967

Signed: Archie Elving
Well Plugging Supervisor

DATE 3/31/67

CONSERVATION DIVISION 3-31-67
Wichita, Kansas

INV. NO. 4980-W