

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-047-28303-0660

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Halliburton Oil Production Co.

Complete Address Box 10 Stafford Kansas 67578

Lease Name English Well No. 1

Location C-SE-SW Sec. 1 Twp. 26S Rge. 16W (East)(West)

County Edwards Total Depth 4450'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated This well had produced oil & then later gas

Plugging Contractor Kelso Casing Pulling

Address Box 176 Chase Kansas 67524 License No. 681

Operation Completed: Hour: 10:30 AM Day: 21 Month: November Year: 19 81

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

There is 454' of 8 7/8" surface casing cement circulated with 250 lbs of cement.
There is 4447' of 4 1/2" production pipe cemented with 100 lbs of cement. There is a
2 stage collar at 2360' cemented with 350 lbs of cement. The pipe was
cemented to 1990'. The perforations were from 2203' to 2207'. 1st
plug sandbed off bottom back to 2150' with 4 lbs of cement. 2nd
plug pumped 5 lbs of hulls & 25 lbs of 3/4" red rubber plug &
pumped 150 lbs of cement on top of it to bring cement to 0'. Cement
used was 50/50 grade 4 3/4" gels 3 3/4" cc. There were 1925' of 4 1/2" production
pipe recovered. Plugging accomplished by Halliburton Co
out of Pratt Kans. Shut in pressure 250 lbs

I hereby certify that the above plugging instructions were given as herein stated.

INVOICED

STATE CORPORATION COMMISSION

Signed: Paul Luthi
Conservation Division Agent

DATE 12-11-81

NOV 24 1981

INV. NO. 8055-W

CONSERVATION DIVISION
Wichita, Kansas

11-24-81