

KANSAS

FORM CP-3  
Rev. 1-8-82

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-047-20575-0000

200 Colorado Derby Building  
Wichita, KS 67202

Operator's Full Name Oil Properties Co. Inc.

Complete Address Box 335 Andover, Kansas 67002

Lease Name Bryant "X" Well No. 2

Location SE-NE-SW Sec. 2 Twp. 26 Rge. 16 (East)(West)

County Edwards Total Depth 4466'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling

Address Box 176 Chase Kansas 67524 License No. 681

Operation Completed: Hour: 1:00 PM. Day: 2 Month: June Year: 1982

Plugging Operations attended by Agent?: All  Part  None

The above well was plugged as follows:

*They set 4461' of 4 1/2" production pipe. They plugged back to 4456' & perforated from 4381' to 4454'. 1st plug sand bottom back to 4350' & put 4 sbp of cement on top of sand. 2nd plug 5 sbp of hulls 25 sbp Jella 140 sbp of cement. They sand & cemented off bottom with bailer & cemented the top by pumping cement down 8 5/8" from top. They recovered 3530' of 4 1/2" production pipe. The plugging was accomplished by Kelso Casing Pulling with Allied Cement pumping the cement. Cement used was 50/50 Pave 2 1/2 Gall and 3% C.C.  
Amount of Surface Casing: 424' of 8 5/8" Cement circulated (over)*

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Paul A. Luthi  
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

6-8-82

Signed: \_\_\_\_\_  
Conservation Division Agent

JUN - 8 1982

JUN - 8

CONSERVATION DIVISION CONSERVATION DIVISION  
Wichita, Kansas Wichita, Kansas

INVOICED

DATE 6-11-82

INV. NO. 404-u

The shut in pressure was 100 lbs they released rubber  
plug following the jet & Halls and followed up  
with the cement.

Paul A. Luthi