

KANSAS

*SP*  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 17 1968  
CONSERVATION DIVISION  
Wichita, Kansas

12-17-68

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

15-155-00082-0500

Operator's Full Name Messman-Rinehart Oil Company

Complete Address: 1432 Wichita Plaza, Wichita, Kansas 67202

Lease Name Pafford Well No. 1

Location NW NW NE Sec. 12 Twp. 26 Rge. 9 (E) (W) X

County Reno Total Depth 3981'

Abandoned Oil Well      Gas Well XX Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Southwest Casing Pulling Co., Inc.

Address: Box 364, Great Bend, Kansas License No. 399

Operation Completed: Hour 11 AM Day 12 Month December Year 1968

The Above well was plugged as follows:

(Hole had been sanded back to 3790' by operator). 5 sacks cement dumped on sand

at 3790'. Rock bridge set from 230' to 220'. 7 sacks cement dumped on bridge and

left to set over-night. Hole bailed dry and cemented with 18 sacks cement (total 25).

Hole filled with mud to 40'. Rock bridge set from 40' to 30' and hole cemented to

base of cellar with 10 sacks cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 12/17/68  
INV. NO. 9026-4

Signed: *J. P. Roberts*  
Well Plugging Supervisor