

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAR 22 1971

CONSERVATION DIVISION
Wichita, Kansas

3-22-71
30027

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Robert F. White 15-155. ~~30093-0000~~

Complete Address 714 Union Center, Wichita, Kansas 67202

Lease Name Snell Well No. 1

Location C SE/4 Sec. 13 Twp. 26 Rge. 9 (E) (W) X

County Reno Total Depth 2412'

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Knight Casing Pulling Co., Inc.

Address Box 405, Chase, Kansas License No. 624

Operation Completed: Hour 4 PM Day 16 Month March Year 1970

The above well was plugged as follows:

Hole filled with sand to 2340'. Casing shot off, and well blew in. Casing circulated
with heavy mud to kill gas. Top of heavy mud at 200'. Set rock bridge from 200' to
190' and hole cemented with 25 sacks cement. Hole filled with mud to 40'. Rock
bridge set from 40' to 30' and hole cemented to base of cellar with 10 sacks cement.

I hereby certify that the above well was plugged as herein stated.

Signed: *William J. Roman*
Well Plugging Supervisor

INVOICED

DATE 3/22/71

PNV. NO. 3432-W