

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-081-20333-00-00

LEASE NAME Ellsaesser "A"

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

660 Ft. from S Section Line

660 Ft. from E Section Line

LEASE OPERATOR Amoco Production Co.

SEC. 22 TWP. 29 SRGE. 33 (E) or (W)

ADDRESS P. O. Box 432 Liberal, KS 67901

COUNTY Haskell

PHONE#(316) 624-6241 OPERATORS LICENSE NO. 5952

Date Well Completed 1-3-86

Character of Well D&A

Plugging Commenced 12-26-85

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 1-3-86

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation None Depth to Top _____ Bottom _____ T.D. 5500

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Kansas City "B"	Water	4666	4768	9-5/8"	1760	None
Marmaton	Water	4768	5004	7"	5550	3050'
Atoka	Water	5100	5214			
Morrow	Water	5214	5500			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Set CIBP at 4150' with 2 sxs cement. Loaded hole with mud. Pumped 20 sxs Gel, followed by 50 sxs cement 2516 to 2350'. Pumped 50 sxs cement 1700 to 1550'. Pumped 40 sxs cement 700 to 560'. Put bridge with 10 sxs cement 40' to 5'. Cut off 9-5/8" 5' below ground level and cement Cap.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Midwest Casing Pulling Service License No. 6497


Address Box F Sublette, KS 67877

STATE OF Kansas COUNTY OF Seward, ss.

P. A. Lehrman (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) P. A. Lehrman

(Address) P. O. Box 432 Liberal, KS 67901



Subscribed and sworn to before me this 10th day of January, 19 86

V. K. Bruce V. K. Bruce

Notary Public
STATE CORPORATION COMMISSION

My Commission Expires: 4-28-89

JAN 13 1986
1-13-86
CONSERVATION DIVISION