

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Reno County, Sec. 1 Twp. 24S Rge. (E) 4W

Location as "NE/CNW&SW" or footage from lines NW NE NW

Lease Owner Leben Drilling, Inc.

Lease Name Seeley Well No. 1

Office Address 905 Central Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed October 22 19 56

Application for plugging filed October 22 19 56

Application for plugging approved October 22 19 56

Plugging commenced October 22 19 56

Plugging completed October 22 19 56

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel E. Durkee

Producing formation _____ Depth to top _____ Bottom: _____ Total Depth of Well 3800 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	590'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud to 310'. Set plug at 310' w/1/2 sack of hulls and 15 sacks of cement. Filled with heavy mud to 15', set plug and ran hulls and cement to surface.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Leben Drilling, Inc. 10-26-56

Address 905 Central Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss. James M. Battin (employee of owner) ~~owner~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James M. Battin

905 Central Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 25th day of October, 19 56

My commission expires July 10, 1957

James Thomas
Notary Public.

PLUGGING
FILE SEC. 1 T. 24 R. 4W
BOOK PAGE 110 LINE 35

CONTRACTOR'S WELL LOG

Leben Drilling, Inc.
Seeley #1
NW NE NW of Sec. 1-24S-4W
Reno County, Kansas

0	105	Surface
105	145	Sand
145	487	Shale and Shells
487	540	Shale and Lime
540	740	Shale and Lime
740	780	Shale and Shells
780	798	Anhydrite
798	1270	Shale and Lime
1270	1560	Lime and Shale
1560	2155	Shale and Lime
2155	2300	Lime and Shale
2300	2725	Shale and Lime
2725	2740	Shale
2740	3100	Shale and Lime
3100	3190	Lime and Shale
3190	3250	Shale
3250	3490	Lime
3490	3520	Lime and Shale
3520	3610	Shale and Lime
3610	3665	Lime and Shale
3665	3715	Shale and Lime
3715	3800	Shale and Lime
	3800	<u>Rotary Total Depth D & A</u>

COMMENCED: October 6, 1956
COMPLETED: October 22, 1956

SURFACE CASING:
Set 8 5/8" at 312' w/ 250
sacks cement plus 2 scks. Ca. Cl.

RECORDED
STATE OF KANSAS
OCT 24 1956
WICHITA COUNTY

State of Kansas)
County of Sedgwick) ss:

I, James M. Battin, do hereby certify that the above and foregoing is a true and correct copy of the log of the Seeley #1, NW NE NW of Section 1-24S-4W, Reno County, Kansas, as reflected by the files of Leben Drilling, Inc..

James M. Battin
James M. Battin

Subscribed and Sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 25th day of October, 1956.

J. Thomas

My commission expires July 10, 1957.

RECEIVED
STATE CORPORATION COMMISSION

OCT 30 1956

CONSERVATION DIVISION
Wichita, Kansas

10-30-56

PLUGGING
FILE SEC 1 T 24 R 4 W
BOOK PAGE 110 LINE 35