

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-155-20,973-000

LEASE NAME Kincaid #1

WELL NUMBER _____

SPOT LOCATION NW NW NE

SEC. 1 TWP. 24 RGE. 4W (E) or (W)

COUNTY Reno

Date Well Completed _____

Plugging Commenced 3/14/85

Plugging Completed 3/18/85

LEASE OPERATOR Excalibur Production Co., Inc.

ADDRESS P.O. Box 278, McPherson, Ks. 67460

PHONE # (316) 241-1265 OPERATORS LICENSE NO. 5330

Character of Well _____
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Wichita

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom T.D. 3358'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				12 3/4	262'	none
				5 1/2"	3354'	2508'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Plugged bottom with sand to 3300' & 5 sacks cement. Shot pipe at 2912' & 2508'. Pulled 59 joints of pipe. Baled hole to 350' & set Rock Bridge, dumped 11 yards Ready-mix.

Plugging complete

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050

Address Box 347, Chase, Ks. 67524

STATE OF Kansas COUNTY OF Rice, ss.

RECEIVED
STATE CORPORATION COMMISSION
3-20-85
MAR 20 1985

R. Darrell Kelso (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


CONSERVATION DIVISION
Wichita, Kansas

(Signature) R. Darrell Kelso


(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 19 day of March, 1985

My Commission expires:



Irene Hoover
Notary Public



Blackstone Drilling, Inc.

Box 1184 • 523 West Kansas • Phone (316) 241-1250
McPHERSON, KANSAS 67460
February 9, 1984

COMPANY: EXCALIBUR PRODUCTION CO., INC.
 CONTRACTOR: BLACKSTONE DRILLING, INC.
 FARM: KINCAID #1
 LOCATION: 990' FNL & 330' FWL NE/4 Section 1-24-4W,
 Reno County, Kansas
 COMMENCED: February 1, 1984
 COMPLETED: February 9, 1984
 ELEVATION:

0	to	150	Sand
150	to	265	Shale
265	to	600	Shale & Lime
600	to	1400	Lime & Shale
1400	to	1690	Shale & Lime
1690	to	2000	Shale
2000	to	2290	Lime & Shale
2290	to	2605	Shale & Lime
2605	to	2862	Lime & Shale
2862	to	3212	Lime
3212	to	3287	Shale & Lime
3287	to	3305	Shale
3305	to	3358	Mississippi
		3358	T. D.

Cut 17" hole to 262' and run 264' of 12 3/4" surface pipe, cemented with 110 sacks of cement at 262'. Plug down at 3:15 P. M., February 1, 1984. Run 3360' of 5 1/2" casing, cemented with 75 sacks of cement at 3354'. Plug down at 5:30 A. M., February 9, 1984.

TOPS: MISSISSIPPI - 3305'

Measurements taken from K. B.

REC'D
STATE CORPORATION COMMISSION

MAR 15 1985

CERTIFICATE

CONF. DIVISION
3-15-85

I, P. E. Plouffe, President of Blackstone Drilling, Inc. do hereby certify that the above and foregoing is a true and correct copy of log on your Kincaid #1, located on the 990' FNL & 330' FWL NE/4 Section 1-24-14W, Reno County, Kansas as reflected by the files of Blackstone Drilling, Inc.

P. E. Plouffe
P. E. Plouffe, President

Subscribed and sworn to before me a Notary Public in and for McPherson County, Kansas this 9th day of February, 1984.

Johnnie L. Schmidt
Johnnie L. Schmidt - Notary Public

	JOHNNIE L. SCHMIDT McPherson County, Kansas My Appt. Exp. June 23, 1985
--	---