


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Reno County, Sec. 14 Twp. 23S Rge. (E) 8 (W)

Location as "NE/CNW%SW%" or footage from lines C NW NW  
Lease Owner Henry Wofford Enterprises  
Lease Name Evarts Well No. 1  
Office Address 1258 Cleveland Wichita, Kans.  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 12-20 1963  
Application for plugging filed 12-20 1963  
Application for plugging approved 12-20 1963  
Plugging commenced 12-20 1963  
Plugging completed 12-20 1963  
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Coleman  
Producing formation Depth to top Bottom Total Depth of Well 3677 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	209'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mud to 200'. plug at 200'. 1/2 sack hulls and 20 sacks of cement. Mud to 40' set top plug. 1/2 sack hulls with 10 sacks cement to top. 2 sacks in rat hole.

RECEIVED  
STATE CORPORATION COMMISSION

DEC 23 1963  
12-23-63  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor SeRoBee Drilling Co., Inc.  
Address 5301 N. Broadway Wichita, Kans.

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
Paul S. Septer (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. SeRoBee Drilling Co., Inc.  
(Signature) Paul S. Septer, President  
5301 N. Broadway Wichita, Kans.

SUBSCRIBED AND SWORN TO before me this 20th day of December, 1963

My commission expires 12-28-66

Phillip D. Hurd  
Notary Public

KANSAS GEOLOGICAL SOCIETY  
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU  
KANSAS GEOLOGICAL SOCIETY BUILDING  
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY Henry Wofford Enterprises

SEC. 14 T. 23S R. 8W

FARM Evarts NO. 1

LOC. C NW NW

TOTAL DEPTH 3677'


COUNTY

COMM. 12-8-63

COMP. 12-20-63

KANSAS

SHOT OR TREATED



CONTRACTOR SeRoBee Drilling Co., Inc.

ISSUED

CASING

20 10  
15 209' W/185 sacks  
12 6  
13 5

ELEVATION 1639 KB

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

RECEIVED  
STATE CORPORATION COMMISSION

DEC 23 1963

12-23-63

CONSERVATION DIVISION  
Wichita, Kansas

0	-	45	Sandy soil
45	-	350	Lime & shale
350	-	860	Shale & shells
860	-	1260	Shale & lime
1260	-	2078	Lime
2078	-	2790	Lime & shale
2790	-	2912	Lime
2912	-	2926	Lime & shale
2926	-	3144	Hebner
3144	-	3445	Lansing- Kansas City
3445	-	3650	Lime
3650	-	3657	Cherty Conglomerate
3657	-	3677	Mississippi Chert
	-	3677	TD

State of Kansas, County of Sedgwick,

I, Paul S. Septer, of the SeRoBee Drilling Co., Inc., state:  
That I have knowledge of the facts, statements and matters herein  
contained and that the same are true and correct.

*Paul S. Septer*

Subscribed and sworn to before me on this 20th day of December,  
1963. My commission expires : 12-28-66.

*Philip W. Hurd*  
Notary