

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, Kansas 67202

Well Plugging Record
K.A.R. -82-3-117

API NUMBER 15-155-214370000
LEASE NAME Louise
WELL NUMBER 1-8

TYPE OR PRINT
NOTICE: Fill out completely and return
to Cons. Div. office within 30 days.

1980 Ft. from South Line of Section
660 Ft. from East Line of Section

LEASE OPERATOR Corsair Energy, LC SPOT LOCATION C Ne Se
ADDRESS 209 E. William, Sutton Place, Suite 220 Section 8 Township 23s Range 8w
CITY, STATE, ZIP Wichita, Kansas 67202 County Reno
PHONE # 316-267-7779 Date Well Completed August 21, 1999
Character of Well Dry and Abandoned Date Plugging Commenced August 21, 1999
(Oil, Gas, D&A, SWD, Input, Water Supply Well) Date Plugging Completed August 22, 1999

The plugging proposal was approved on August 19, 1999 at 9:30 am (date)
by Dave Wertz (KCC District Agent's Name)

Is ACO-1 Filed? ? If not, is well log attached? Yes
Producing Formation(s) D&A Depth to Top Bottom T.D. 3760

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
Surface Soil and clay	Top soil and clay	0	45	and		
Fine sand to sand and gravel	Sand and gravel	45	81	and		
Redbeds	Siltstone/Shale	81	210	8-5/8"	194.00	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Received plugging orders from Dave Wertz at 9:30am on 8-19-99

Plugged well as follows using 60/40 Poz 4% Gel:

heavy mud to 750' then 35 sacks, heavy mud to 250' then 35 sacks, heavy mud to 25'

then 25 sacks. 15 sacks in the rathole, 10 sacks in mousehole, 10 sacks in water well.

Plugging completed at 1:00am on 8-22-99 by United. Ticket # 1662.

Name of Plugging Contractor Sterling Drilling Company
Licence No. 5142
Address P.O. Box 1006 City: Pratt State: Kansas Zip 67124

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Corsair Energy, LC (Operator)


STATE OF KANSAS COUNTY OF PRATT, ss.

Steve E. McClain, Agent (Employee of Operator or (Operator) of above described well, being first
duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of
the above described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]
(Steve E. McClain, President of Sterling Drilling Company)

(Address) P.O. Box 1006 City: Pratt State: Kansas Zip 67124

SUBSCRIBED AND SWORN TO me this 30th day of Sept., 19 99



[Signature]
(Notary Public)

10-1-99
RECEIVED
KANSAS CORP COM
1999 OCT -1 A 11:32

My Commission Expires: _____

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 155-214370000

LEASE NAME Louise

WELL NUMBER 1-8

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

1980 Ft. from S Section Line

660 Ft. from E Section Line

SEC. 8 TWP. 23 RGE. 8W (E) or (W)

COUNTY Reno

LEASE OPERATOR Corsair Energy, LC

ADDRESS 209 E William #220 Wichita KS 67202

PHONE# (316) 267 7779 OPERATORS LICENSE NO. 5058

Date Well Completed 8/22/99

Character of Well D&A

Plugging Commenced 8/22/99

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 8/22/99

The plugging proposal was approved on 8/19/99 (date)

by Dave Wertz (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? _____

Producing Formation NA D&A Depth to Top _____ Bottom _____

Show depth and thickness of all water, oil and gas formations.

T.D.
RECEIVED
 KANSAS CORPORATION COMMISSION
9-28-99
 SEP 28 1999

OIL, GAS OR WATER RECORDS _____ CASING RECORD _____

Formation	Content	From	To	Size	Put In	Pulled out

CONSERVATION DIVISION
 WICHITA KS

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Heavy mud from 3760' to 1250', then 35 sks, Heavy mud from 750' then 35 sks, heavy mud to 250' then 35 sks, heavy mud to 25' then 25 sks.
15 sks in rathole 10 sks in mousehole. 10 sks in water well.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sterling Drilling, Inc. License No. 5142

Address Box 1006 Pratt KS 67124-1006

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Corsair Energy, LC

STATE OF Kansas COUNTY OF Sedgwick, ss.

James G. Collins


(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 209 E William #220 Wichita KS 67202

SUBSCRIBED AND SWORN TO before me this 27 day of September, 19 99



Expires: 10/22/02

Notary Public

Sterling Drilling Company, Rig #4

Box 1006, Pratt, Kansas 67124-1006
Office Phone (316) 672-9508, Fax 672-9509

SAMPLE LOG

Louise 1-8

LOCATION: C Ne Se Section 8 T 23s R 8w
API: 15-155-214370000 Reno County, Kansas

OWNER: Corsair Energy, LC
CONTRACTOR: Sterling Drilling Company, Rig #4

COMMENCED: 16-Aug-99
COMPLETED: 22-Aug-99

TOTAL DEPTH: **DRILLER** 3760 FEET
LOGGER 3759 FEET

Ground Elevation: 1662
KB Elevation: 1671

LOG

0 - 160 FEET Top Soil and Clay
160 - 1250 FEET Redbeds and Salt/Anhydrites
1250 - 3760 FEET Limestone/Shale and Chert

CASING RECORDS

Surface/Production Casing Data:

Spud @ 7:30 am on 08-16-99. Drilled 12 1/4" hole to 210'. Ran 5 joints of 8-5/8" surface casing 194.00' set at 206' KB. Cemented with 175 sacks 60/40 Poz, 2% Gel, 3% CC. Plug down at 12:30pm on 08-16-99 by United. Good returns. Ticket # 1961.

Received plugging orders from Dave Wertz at 9:30am on 8-19-99

Plugged well as follows using 60/40 Poz 4% Gel:

Began plugging at 11:30pm on 8-21-99. Heavy mud from 3760' to 1250' then 35 sacks, heavy mud to 750' then 35 sacks, heavy mud to 250' then 35 sacks, heavy mud to 25' then 25 sacks. 15 sacks in the rathole, 10 sacks in mousehole, 10 sacks in water well.

Plugging completed at 1:00am on 8-22-99 by United. Ticket # 1662.

DEVIATION SURVEYS

1/2 degree(s) at 210 feet
1-1/4 degree(s) at 3348 feet

10-1-99

RECEIVED
KANSAS CORP COMM
1999 OCT -1 A 11:32