


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Reno County, Sec. 32 Twp. 23S Rge. 8 (7) W (W)  
Location as "NE/CNW/SW" or footage from lines NE NE NW  
Lease Owner Bell Oil & Gas Company  
Lease Name Schmucker Well No. 1  
Office Address Box 2007, Tulsa, Oklahoma  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 10-4-1956  
Application for plugging filed 10-4-1956  
Application for plugging approved 10-4-1956  
Plugging commenced 10-4-1956  
Plugging completed 10-4-1956  
Reason for abandonment of well or producing formation Dry hole

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee  
Producing formation Depth to top Bottom Total Depth of Well 4174 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	230	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy rotary mud to 185', set plug and cemented with 15 sacks cement. Filled hole with heavy rotary mud to 20', set plug and cemented to bottom of cellar with 5 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Transit Corporation  
Address 1516 Liberty Bank Building, Oklahoma City, Oklahoma

STATE OF OKLAHOMA, COUNTY OF OKLAHOMA, ss.  
G. W. Dodson, agent of (Bell Oil & Gas Company) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature): G. W. Dodson  
Oklahoma City, Oklahoma  
(Address)

SUBSCRIBED AND SWORN TO before me this 10th day of October, 1956

Francis C. Terry  
STATE CORP. Notary Public.

My commission expires March 31, 1960.

PLUGGING  
FILE SEC. 32. T. 23. R. 8. W.  
BOOK PAGE 105 LINE 27

OCT 12 1956 10-12-56  
CONSERVATION DIVISION  
Wichita, Kansas

15-155-00005-0000

BELL OIL & GAS COMPANY  
SCHMUCKER #1

NE NE NW Sec. 32-23S-8W, Reno Co., Kansas

Total Depth: 4174'  
Commenced: 9-19-56  
Completed: 10-4-56

Elevation: 1673' DF  
Casing: 8 5/8" @ 225'  
150 sacks Pozmix

<u>Formation</u>	<u>Depth</u>	<u>Formation</u>	<u>Depth</u>
Clay & Sand	115	Lime, K. C.	3317
Red Rock	225	Lime, Lansing	3460
Shale & Shells	600	Lime & Shale	3535
Shells & Red Bud	800	Lime	3630
Shells & Shale	1000	Lime & Shale	3678
Salt & Shale Shells	1370	Shale & Chert	3710
Sandy Lime & Shale	1520	Lime	3745
Shale	1865	Lime & Chert	3807
Shale & Lime Streaks	1990	Lime & Shale	3873
Shale	2715	Shale	3945
Lime & Shale	2878	Shale & Broken Sand	4059
Lime	2955	Arbuckle Lime	4174
Shale & Lime	3029	Total Depth	4174
Shale & Broken Lime	3200		
Lime	3263		

I hereby certify the foregoing to be a true and correct Driller's Log to the best of my knowledge.

C. W. Dodson  
C. W. Dodson

Subscribed and sworn to before me this 13th day of October, 1956.

My commission expires: March 31, 1960.

RECEIVED  
STATE CORPORATION COMMISSION

Francis C. Lury  
Notary Public

OCT 12 1956 10-12-56

REGISTRATION DIVISION  
Wichita, Kansas

**PLUGGING**  
FILE SEC. 22 T. 23 R. 8W.  
BOOK PAGE 105 LINE 27