

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, Kansas 67202

**Well Plugging Record**  
**K.A.R. -82-3-117**

API NUMBER 15-155-21446-0000  
LEASE NAME Welker  
WELL NUMBER 1-16

TYPE OR PRINT  
NOTICE: Fill out completely and return  
to Cons. Div. office within 30 days.

700 Ft. from North Line of Section  
2300 Ft. from West Line of Section

LEASE OPERATOR Corsair Energy, LC SPOT LOCATION 40'S & 10'W of E1/2 of  
ADDRESS 209 E. William, Sutton Place, Suite 220 Section 16 Township 23s Range 8w  
CITY, STATE, ZIP Wichita, Kansas 67202 County Reno  
PHONE # 316-267-7779 Date Well Completed August 13, 2000  
Character of Well Dry and Abandoned Date Plugging Commenced August 13, 2000  
(Oil, Gas, D&A, SWD, Input, Water Supply Well) Date Plugging Completed August 13, 2000

The plugging proposal was approved on August 12, 2000 at 2:15 pm (date)  
by Dave Wertz (KCC District Agent's Name)

Is ACO-1 Filed? ? If not, is well log attached? Yes  
Producing Formation(s) D&A Depth to Top Bottom T.D. 3770

Show depth and thickness of all water, oil and gas formations.

**OIL, GAS OR WATER RECORDS**

**CASING RECORD**

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
Surface Soil and clay	Top soil and clay	0	38			
Fine sand to sand and gravel	Sand and gravel	38	82			
Redbeds	Siltstone/Shale	82	210	8-5/8"	194.91	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from        feet to        feet each set.

Received plugging orders from Dave Wertz at 2:15 pm on 9-12-00.

Plugged well as follows using 150 sacks 60/40 Poz 4% Gel: Began plugging at 9:20am on 9/13/00.

Heavy mud from 3770' to 1250' then 35 sacks, heavy mud to 750' then 35sx, heavy mud to 250'

then 35 sacks, heavy mud to 60' then 25 sx, cement did circulate, 15sx in rathole, 10sx in mousehole.

Plugging completed at 11:00am on 9-13-00 by Allied. Ticket # 4271.

Name of Plugging Contractor Sterling Drilling Company

Licence No. 5142

Address P.O. Box 1006 City: Pratt State: Kansas Zip 67124

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Corsair Energy, LC (Operator)

STATE OF KANSAS COUNTY OF PRATT, ss.


RECEIVED  
STATE CORPORATION COMMISSION

Gary M. Talbott, Agent (Employee of Operator or (Operator) of above described well, being first  
duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of  
the above described well as filed that the same are true and correct, so help me God.

(Signature) Gary M. Talbott  
(Gary M. Talbott, Vice- President of Sterling Drilling Company)

(Address) P.O. Box 1006 City: Pratt State: Kansas Zip 67124

SUBSCRIBED AND SWORN TO me this 14th day of Sept., 192000



Pamela S. Fields  
(Notary Public)

My Commission Expires: \_\_\_\_\_

# Sterling Drilling Company, Rig #4

Box 1006, Pratt, Kansas 67124-1006  
Office Phone (316) 672-9508, Fax 672-9509

## SAMPLE LOG

## Welker 1-16

**LOCATION:** 40'S &10'W of E1/2 of Section 16 T 23s R 8w  
**API:** 15-155-21446-0000 Reno County, Kansas

**OWNER:** Corsair Energy, LC  
**CONTRACTOR:** Sterling Drilling Company, Rig #4

**COMMENCED:** 07-Sep-00  
**COMPLETED:** 13-Sep-00

**TOTAL DEPTH:** **DRILLER** 3770 FEET  
**LOGGER** 3750 FEET

**Ground Elevation:** 1656  
**KB Elevation:** 1665

### LOG

0 -	80 FEET	Top Soil and Clay
80 -	114 FEET	Sand
114 -	1500 FEET	Redbeds, Shales, Anhydrite and Salt
1500 -	3770 FEET	Limestone/Shale and Chert

### CASING RECORDS

#### Surface/Production Casing Data:

Spud @ 10:15 am on 09-07-00. Drilled 12 1/4" hole to 210'. Ran 5 joints of 20# 8-5/8" surface casing, tally 194.91' set at 206' KB. Cemented with 175 sacks 60/40 Poz, 2% Gel, 3% CC. Plug down at 3:15pm on 09-07-00 by Allied. Good returns. Ticket # 4109.

Received plugging orders from Dave Wertz at 2:15 pm on 9-12-00.

Plugged well as follows using 150 sacks 60/40 Poz 4% Gel:

Began plugging at 9:20am on 9-13-00. Heavy mud from 3770' to 1250' then 35 sacks, heavy mud to 750' then 35 sacks, heavy mud to 250' then 35 sacks, heavy mud to 60' then 25 sacks, cement did circulate, 15 sacks in the rathole, 10 sacks in mousehole.

Plugging completed at 11:00am on 9-13-00 by Allied. Ticket # 4271.

### DEVIATION SURVEYS

1/4 degree(s) at	210	feet
2 degree(s) at	3235	feet
2 1/2 degree(s) at	3472	feet
3/4 degree(s) at	3770	feet

RECEIVED  
STATE CORPORATION COMMISSION

SEP 15 2000

CONSERVATION DIVISION  
Topeka, Kansas