

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-147-20934-0000

SE/4, Sec. 2, T 26 S, R. 16 W/4  
SWSESE feet from N/S section line

TECHNICIAN'S PLUGGING REPORT

\_\_\_\_\_ feet from W/E section line

Operator License # 8061

Lease Name BRYANT Well #3

Operator: Oil Producers, Inc.  
Name & Address of Kansas  
Box 39A, RT #1  
Haviland, KS 67059

County EDWARDS

Well Total Depth 4487 feet #145.83

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 7/8 feet 427

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 176, Chase, KS 67524

Company to plug at: Hour: 9:30 AM Day: 21 Month: March Year: 1983

VERBAL PLUGGING ORDERS GIVEN TO Bob Brenneman

(company name) Kelso (phone) \_\_\_\_\_

were: use 50/50 lb zinc, 2% gel - 3% cc. sand  
in down to 4400' w/ 5 sy cement. Pump 3 sy. hulls,  
20 sy gel, 70 sy cmt. Then follow w/ 10 sy gel,  
1 sy hulls, release plug and finish w/ 110 sy cmt.

Signed R. Braithwaite  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:45 AM Day: 21 Month: March Year: 1983

ACTUAL PLUGGING REPORT Plugged as ordered. Cementing by  
Allied Cement, May. pump press. @ 500#, shut  
in press. @ 50#.

Remarks: 4 1/2" @ 4482' - rec. 2827 - perf. @ 4449-4453

Mr. Steve Durrant observed plugging.  
I hereby certify that the above plugging instructions were given as herein stated  
and that I (did / did not) observe this plugging.

INVOICED RECEIVED  
DATE 4-11-83 STATE CORPORATION COMMISSION  
INV. NO. 3931-42 MAR 23 1983

Signed R. Braithwaite  
(TECHNICIAN)