

1-26-88

190

R

To: 1 120062
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-047-20,449-0600
C N/2 SE/4, SEC. 2, T 26 S, R 16 W/EX

TECHNICIAN'S PLUGGING REPORT

Operator License # 8061
Operator: Oil Producers Inc. of Kansas
Name & Address: P.O. Box 8647
Wichita, KS 67208

1980 feet from S section line
1320 feet from E section line
Lease Name Wood Well # A #1
County Edwards 144.63
Well Total Depth 4450 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 420

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Rockhold Engineering Inc. License Number 5111
Address Box 698, Great Bend, KS 67530

Company to plug at: Hour: 11:30 a.m. Day: 26 Month: 1 Year: 19 88

Plugging proposal received from Jack Smith
(company name) Rockhold Engineering, Inc. (phone) 316-792-2506

were: 4 1/2" at 4449' PBTD 4426' Perfs at 4393-4405'
1st plug sand back to 4330' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 125 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:30 p.m. Day: 26 Month: 1 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 4330' and dumped 4 sx cement on top of sand
through bailer,
2nd plug pumped into 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement,
10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Pumping pressure 0-400 psi and shut in 50 psi.

Remarks: Used 60/40 Pozmix 6% gel by Howco. Recovered 3435' of 4 1/2" casing.
(if additional description is necessary, use BACK of this form)
RECEIVED STATE CORPORATION COMMISSION

FEB 03 1988

do not observe this plugging.

INVOICED
DATE 2-4-88
INV. NO. 19724

Signed Dean Rankin (TECHNICIAN)