

6-29

To: 120271  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 047-20,747-0000

NW NW NE, SEC. 2, T 26 S, R 16 W/E

4950 feet from S section line

2240 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8061

Lease Name Cudney "A" Well # 3

Operator Name & Address Oil Producers, Inc. of Kansas

County Edwards 145.54

P.O. Box 8647

Well Total Depth 4478 feet

Wichita, KS 67208

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 452

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Rockhold Engineering, Inc. License Number 5111

Address Box 698, Great Bend, KS 67530

Company to plug at: Hour: 3 p.m. Day: 29 Month: 6 Year: 19 89

Plugging proposal received from Jim Rockhold

(company name) Rockhold Engineering, Inc. (phone) 316-792-2506

were: 4 1/2" at 4476' PBD 4420' Perfs at 4362-71'

1st plug sand back to 4300' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 125 sx cement.

Plugging Proposal Received by Stephen J. Pfeifer  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part  None \_\_\_\_\_

Operations Completed: Hour: 4 p.m. Day: 29 Month: 6 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded back 4 1/2" casing to 4312' and dumped 4 sx cement  
on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 4 sx hulls, 10 sx gel, 50 sx cement, 10  
sx gel, 1 sx hulls, released 8 5/8" wiper plug and pumped 125 sx cement

Pumping pressure 0-300 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3215' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

**INVOICED**

DATE 7-6-89

Signed Dean Rankin  
(TECHNICIAN)

INV. NO. 25218

RECEIVED  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
Wichita, Kansas  
III - 5 1989