

1 080347

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 047-21,178.-0000

C SE SE NE, SEC. 2, T 26 S, R 16 W/K

2970 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5393

Lease Name Woods Well # 4

Operator: A. L. Abercrombie, Inc.

County Edwards 144.79

Name & Address 801 Union Center

Well Total Depth 4455 feet

Wichita, KS 67202

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 473 ✓

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 11:00 am Day: 14 Month: March Year: 19 85

Plugging proposal received from Bob Brenneman

(company name) Kelso (phone) 316-938-2457

were: 5 1/2" set at 4453' PBD 4419' Perfs at 4398-4400

1st plug sand back to 4350' and dump 5 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 150 sx cement.

Plugging orders given by Paul A. Luthi

Plugging Proposal Received by J. A. [Signature] (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 12:15 pm Day: 14 Month: March Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 4350' and dumped 5 sx cement on top of sand through bailer, 2nd plug squeezed well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped an additional 150 sx cement.

RECEIVED STATE CORPORATION COMMISSION

Maximum Pressure 350 psi and shut in 150 psi

MAR 25 1985 3-25-1985

Remarks: Recovered 3036' 5 1/2" casing. Used 60/40 Pozmix 602% by Sun. (If additional description is necessary, use BAOR form.)

INVOICED

DATE 3-26-85 INV. NO. 7410

Signed J. A. [Signature] (TECHNICIAN)