

12-22-87

15-047-20246-0000

1 061053

API NUMBER 15-Drill Completion Date 3/23/77

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NE NE SW, SEC. 3, T 26 S, R 16 W/E
2310 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5992

Lease Name Gibson Well # 3

Operator: Patton Oil Company

County Edwards 145.02

Name & Address 672 West 4th Street

Well Total Depth 4462 feet

Hoisington, KS 67544

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 381

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 8:15 a.m. Day: 22 Month: 12 Year: 19 87

Plugging proposal received from Bill Fulls

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2457

were: 5 1/2" at 4461' PBTD 4450' Perf at 4416'(Top) Elevation 2074'GL

1st plug sand back to 4365' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 120 sx cement.

Plugging Proposal Received by Duane Rankin & Paul Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 9 a.m. Day: 22 Month: 12 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug sanded back to 4365' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8" wiper plug and pumped 120 sx cement.

Maximum pressure 200 psi and shut in 50 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2478' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

STATE CORPORATION COMMISSION
Wichita, Kansas
DEC 29 1987
12-29-1987
1987

INVOICED

DATE 1-7-88

INV. NO. 19898

Signed Paul A. Luthi (TECHNICIAN)