

1-12

i 120209

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-047-20,468-0000
SW NW SE, SEC. 3, T 26 S, R 16 W/EX

TECHNICIAN'S PLUGGING REPORT

Operator License # 5992

1650 feet from S section line
2310 feet from E section line

Operator: Patton Oil Company
Name & Address: 672 West 4th Street
Hoisington, KS 67544

Lease Name Gibson Well # 8
County Edwards 144.72
Well Total Depth 4453 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 436

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050
Address Box 347, Chase, KS 67524

Company to plug at: Hour: 9 a.m. Day: 12 Month: 1 Year: 19 89

Plugging proposal received from Bill Fulls
(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2457

were: 5 1/2" at 4452' cemented w/125 sx PBTD 4420' Perfs at 4370-75'
1st plug sand back to 4320' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 120 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:45 a.m. Day: 12 Month: 1 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 4320' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 120 sx cement.

Pumping pressure 0-400 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2400' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 1-20-89
INV. NO. 23745

RECEIVED
STATE CORPORATION COMMISSION
JAN 17 1989
1-17-1989
CONSERVATION DIVISION
Wichita, Kansas

Signed Duan Bank (TECHNICIAN)