

To: 1 090457 8-22  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-047-20,469-00-00  
NW SW SW, SEC. 3, T. 7 S, R. 16 W  
990 feet from S section line  
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 9449  
Operator: Great Eastern Energy  
Name: Great Eastern Energy  
Address: 672 W. 4th  
Hoisington, KS 67544

Lease Name Gibson Well # 9  
County Edwards 143.62  
Well Total Depth 4419 ft  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 411

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050  
Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 11 a.m. Day: 22 Month: 8 Year: 1994

Plugging proposal received from Bill Reed  
(company name) Great Eastern Energy (phone) 316-653-2277

Work: 5 1/2" at 4410' w/125 sx cement, Open hole 4410-19'  
1st plug sand back to 4360' and dump 5 sx cement on top of sand through bailer.  
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper  
plug and pump 150 sx cement.

Plugging Proposal Received by Steve Middleton  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None

Operations Completed: Hour: 11:45 a.m. Day: 22 Month: 8 Year: 1994

ACTUAL PLUGGING REPORT 1st plug sanded back to 4360' and dumped 5 sx cement on top of sand  
through bailer,

2nd plug pumped 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls. released  
8 5/8" wiper plug and pumped 150 sx cement,

Maximum pressure 400 psi and shut in 100 psi.

8-25-1994  
RECEIVED  
STATE CORPORATION COMMISSION

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2200' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this report.)

**INVOICED**  
AUG 29 1994

DATE \_\_\_\_\_  
INV. NO. 41078

Signed [Signature]  
(TECHNICIAN)