

To: 1 120703 4-16 API NUMBER 15-047-20,518-0000 119R  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION Irr. Sec. NW, SEC. 3, T. 26 S, R. 16 W/E  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5992  
Operator: Patton Oil Company  
Name: Patton Oil Company  
Address: 672 W. 4th St.  
Hoisington, KS 67544  
Lease Name Southwest College Well # 1  
County Edwards 143.97  
Well Total Depth 4430 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 435

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050  
Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 9:30 a.m. Day: 14 Month: 4 Year: 1992

Plugging proposal received from Mike Kelso  
(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

Work: 5 1/2" at 4418' w/125 sx cement, Open hole from 4418-30'  
1st plug sand 5 1/2" casing back to 4360' and dump 5 sx cement on top of sand through bailer,  
2nd plug pump 25 sx cement at 1500-1600' where parted,  
3rd plug pump 50 sx cement at 1000', 4th plug at 475' with 50 sx cement,  
5th plug at 40' with 10 sx cement.

Plugging Proposal Received by Case Morris  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11 a.m. Day: 16 Month: 4 Year: 1992

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 4360' and dumped 5 sx cement  
on top of sand through bailer, casing parted at 1500',  
2nd plug spotted 25 sx cement at 1500', 3rd plug layed down 5 1/2" casing to 1000' and  
spotted 50 sx cement, 4th plug layed down 5 1/2" casing to 500' and spotted 50 sx cement,  
5th plug layed down all 5 1/2" casing and pumped into 8 5/8" surface casing with 300 lbs.  
hulls and 140 sx cement. Pumping pressure 0-300 psi and shut in 100 psi. (Over)

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2000' of 5 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED (If additional description is necessary, use BACK of this form.) Observe this plugging.

DATE 5-5-92  
INV. NO. 35147

Signed Deanna Roubin 4-24-1992  
(TECHNICIAN)

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
Wichita, Kansas  
APR 24 1992

There was 500' more casing in the hole than estimated. Ran line on plug after spotting plug at 500'. Ran line to 540' and hit cement plug.