

To: 1 040629 2-25  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-047-20,519-0000 165R

TECHNICIAN'S PLUGGING REPORT

Operator License # 5992  
Operator: Patton Oil Company  
Name & Address 672 W. 4th St.  
Hoisington, KS 67544

Irr. Sec. SW, SEC. 3, 'T. 26 S, R 16 W/E  
2535' S of NL feet from XX section line  
330' E of WL feet from E section line  
Lease Name SW College Well # 2  
County Edwards 143.42  
Well Total Depth 4413 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 8 5/8 feet 431

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 10:30 a.m. Day: 25 Month: 2 Year: 19 92

Plugging proposal received from Bill Reed

(company name) Patton Oil Company (phone) 316-653-2277

were: 5 1/2" at 4410' w/125 sx cement, PBTD 4089', Perfs at 4052-57'

1st plug sand back to 4000' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, and 120 sx cement.

RECEIVED  
MAR - 2 1992  
3-2-1992  
STATE CORPORATION COMMISSION  
Wichita, Kansas

Plugging Proposal Received by Steve Pfeiffer  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 11:15 a.m. Day: 25 Month: 2 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug sanded back to 4000' and dumped 5 sx cement on top of sand bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, and 120 sx cement.

Maximum pressure 800 psi and shut in 100 psi.

(Pumped through swedge-left out wiper plug. Collar egged-couldn't get plug container started straight.)

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2900' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

**INVOICED**  
I (and my assistants) observe this plugging.

DATE 3-9-92  
INV. NO. 34694

Signed Stephen J. Pfeiffer  
(TECHNICIAN)