

To: 1051526  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 047-20,539-0000  
NW NW SW, SEC. 3, T. 26 S, R. 16 W

TECHNICIAN'S PLUGGING REPORT

Operator License # 5992  
Operator: Patton Oil Company  
Name & Address 672 W. 4th  
Hoisington, KS 67544

2310 feet from S section line  
4950 feet from E section line  
Lease Name Gibson Well # 10  
County Edwards 144.78  
Well Total Depth 4454 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 433

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050  
Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 1:30 p.m. Day: 3 Month: 2 Year: 19 92

Plugging proposal received from Bill Reed  
(company name) Patton Oil Co. (phone) 316-653-2277

were: 5 1/2" at 4452', Open hole from 4452-56'  
1st plug sand back to 4400' and dump 5 sx cement on top of sand through bailer,  
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"  
wiper plug and pump 150 sx cement.

Plugging Proposal Received by Case Morris  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 3:00 p.m. Day: 3 Month: 2 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug sanded back to 4400' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8"  
wiper plug and pumped 150 sx cement.  
Maximum pressure 300 psi and shut in 50 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2400' of 5 1/2" casing.

(If additional description is necessary, use BACK of this form.) 2-6-1992  
observe this plugging.

INVOICED  
DATE 2-12-92  
INV. NO. 34526

Signed Richard M. Lacey  
(TECHNICIAN)

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 06 1992  
CONSERVATION DIVISION  
WICHITA, KANSAS