

To: 1 120664
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

12-16
API NUMBER 15- 047-20,543-000 90 R

SE SW SW, SEC. 3, T 26 S, R 16 W/E

330 feet from S section line
4290 feet from E section line

Lease Name Gibson Well # 11
County Edwards

Well Total Depth 4404 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 445

TECHNICIAN'S PLUGGING REPORT
Operator License # 5992
Operator: Patton Oil Company
Name & Address: 672 W. 4th St.
Hoisington, KS 67544

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Pipe Recovery Inc. License Number 30752

Address P.O. Box 7, Great Bend, KS 67530

Company to plug at: Hour: 8:30 a.m. Day: 16 Month: 12 Year: 19 91

Plugging proposal received from Rick Davis

(company name) Pipe Recovery, Inc. (phone) 316-793-3922

were: 5 1/2" at 4386' w/125 sx cement, PBSD 4390', Open hole 4386-4404'

1st plug sand back to 4336' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 150 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 10:30 a.m. Day: 16 Month: 12 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 4336' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 350 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 150 lbs. hulls, released 8 5/8" wiper plug and pumped 150 sx cement. Pumping pressure 0-400 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2419' of 5 1/2" casing. (if additional description is necessary, use BACK of this form.)

INVOICED (copy of invoice to be observed) STATE CORPORATION COMMISSION

DATE 1-7-92 DEC 18 1991
INV. NO. 34223 CONSERVATION DIVISION WICHITA, KANSAS

Signed [Signature] (TECHNICIAN)