

To: 1 120701  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 047-20,556 -6000 75 R  
SW SW NW, SEC. 3, T. 26 S, R. 16 W/R  
2970 feet from S section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5992

Operator: Patton Oil Company  
Name & Address 672 W. 4th St.  
Holsington, KS 67544

4950 feet from E section line  
Southwest College

Lease Name \_\_\_\_\_ Well # 3  
County Edwards

Well Total Depth 4435 1.44.13 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 440

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 1:30 p.m. Day: 14 Month: 4 Year: 19 92

Plugging proposal received from Mike Kelso

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 5 1/2" at 4429', Open hole 4429-35'

1st plug sand 5 1/2" casing back to 4375' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 150 sx cement.

Plugging Proposal Received by Case Morris  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 3 p.m. Day: 14 Month: 4 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 4375' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 150 sx cement.  
Pumping pressure 0-200 psi and shut in 0 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2400' of 5 1/2" casing.  
(if additional description is necessary, use BACK of this form.)

**INVOICED**  
Please observe this plugging.

DATE 4-28-92

Signed Case Morris  
(TECHNICIAN)

INV. NO. 35086