

1 061049

12-22-87

15-047-20571-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-300' W
Drill Completion Date 10/18/79
NE NE SW, SEC. 3, T 26 S, R 16 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5992

Operator: Patton Oil Company
Name & Address: 672 West 4th Street
Hoisington, KS 67544

2310 feet from S section line
3270 feet from E section line

Lease Name Gibson Well # 13

County Edwards 143.39

Well Total Depth 4412 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 407

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 9:15 a.m. Day: 22 Month: 12 Year: 19 87

Plugging proposal received from Bill Fulls

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2457

were: 5 1/2" at 4410' PBSD 4419' Open hole from 4412-19'

1st plug sand back to 4350' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 120 sx cement.

Plugging Proposal Received by Paul Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All x Part None

Operations Completed: Hour: 9:45 a.m. Day: 22 Month: 12 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug sanded back to 4350' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, and 120 sx cement.

Maximum pressure 400 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2408' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

12-29-1987
STATE OF KANSAS
RECEIVED
DEC 29 1987
CONSERVATION DIVISION
WICHITA, KANSAS

INVOICED

(If desired, LICENSEE observe this plugging.)

Signed Paul A. Luthi (TECHNICIAN)

DATE 1-7-88

INV. NO. 19399