

To: 1 040630 2-25
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-047-20,572-6060 166R

Lot 4, SEC. 3, T. 26 S, R 16 W/E
1875' S of NL feet from X section line
330' E of WL feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5992

Lease Name SW College Well # 4
County Edwards 144.00

Operator: Patton Oil Company
Name:
Address 672 W. 4th St.
Hoisington, KS 67544

Well Total Depth 4431 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 456

Abandoned Oil Well Gas Well Input Well SWD Well O&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 11:45 a.m. Day: 25 Month: 2 Year: 19 92

Plugging proposal received from Bill Reed

(company name) Patton Oil Co. (phone) 316-653-2277

were: 5 1/2" at 4423' w/125 sx cement, Open hole at 4423-31'

1st plug sand back to 4370' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 120' sx cement.

RECEIVED
STATE CORPORATION COMMISSION
3-2-1992
MAR - 2 1992

Plugging Proposal Received by

Richard Lacey
(TECHNICIAN) - JUN
Wichita, Kansas

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 12:30 p.m. Day: 25 Month: 2 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug sanded back to 4370' and dumped 5 sx cement on top of sand bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 120 sx cement.

Maximum pressure 300 psi and shut in 50 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2000' of 5 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED
Observe this plugging.

DATE 3-8-92
INV. NO. 34695

Signed Stephen J. Pfeiffer
(TECHNICIAN)