

120700

4-14

API NUMBER 15- 047-20,573-0000

76R

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

Lot #4 NW/4, SEC. 3, T. 26 S, R. 16 W/E  
1215 feet from N & section line  
330 feet from W & section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5992  
Operator: Patton Oil Company  
Name & Address: 672 W. 4th St.  
Hoisington, KS 67544

Lease Name Southwest College Well # 5  
County Edwards 145.53  
Well Total Depth 4478 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 461

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050  
Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 12:30 p.m. Day: 14 Month: 4 Year: 19 92

Plugging proposal received from Mike Kelso

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 5 1/2" at 4476' w/125 sx cement. PBSD 4455'. Perfs at 4420-25'  
1st plug sand 5 1/2" casing back to 4370' and dump 5 sx cement on top of sand through bailer,  
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 150 sx cement.

Plugging Proposal Received by Case Morris (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 1:30 p.m. Day: 14 Month: 4 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 4370' and dumped 5 sx cement on top of sand through bailer,  
2nd plug pumped into 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 150 sx cement.  
Pumping pressure 0-200 psi and shut in 0 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3200' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 4-28-92

INV. NO. 35087

Signed [Signature] (TECHNICIAN)