

1-040819

1-11

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-047-20,594-5000

NW SW NE /4 SEC. 03, 26 S, 16 W
3630 feet from S section line
2310 feet from E section line

Operator license# 9449 Lease Cudney well # 1
Operator: Great Eastern Energy/Devel. County Edwards

Address: 672 W. 4th St. Well total depth 4478 feet ^{145.54}
Hoisington, KS 67544 Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 468 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Kelso Casing Pulling, Inc. License# 6050

Address: P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 2:30 pm Day: 11 Month: January Year: 1994

Plugging proposal received from: Vernon Duntz, Jr.

Company: Kelso Casing Pulling, Inc. Phone: 316-938-2943

Were: 5 1/2" at 4477' w/125 sx cement, PBTD 4100', Perfs at 4060-69'
1st plug sand back to 4000' and dump 5 sx cement on top of sand through bailer,
2nd plug pump down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx
cement, 10 sx gel, 100 lbs. hulls, release 8 5/8" wiper plug and pump 150 sx
cement.

Plugging Proposal Received by: Steve Middleton
Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 3 p.m., Day: 11, Month: January, Year: 1994

Actual plugging report: 1st plug sanded back to 4000' and dumped 5 sx cement on
top of sand bridge through bailer,
2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx
cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 150 sx
cement.
Maximum pressure 400 psi and shut in 50 psi.

RECEIVED
STATE CORPORATION COMMISSION

JAN 20 1994

INVOICED
Remarks: used 60/40 Pozmix 6% gel by Allied. Recovered 2800 of 1 1/2" casing.

DATE JAN 21 1994
I did X observe the plugging.
BY NO. 39752

Stephen J. Pfeiffer