

To: 1 120865
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

12-16 91CR
API NUMBER 15-047-20,953-000
SW SE NW, SEC. 3, T 26 S, R 16 W E

TECHNICIAN'S PLUGGING REPORT
Operator License # 5992
Operator: Patton Oil Company
Name & Address: 672 W. 4th St.
Hoisington, KS 67544

2970 feet from S section line
3630 feet from E section line
Lease Name Southwest College Well # B-9
County Edwards 143.32
Well Total Depth 4410 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 463

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Pipe Recovery Inc. License Number 30752

Address P.O. Box 7, Great Bend, KS 67530

Company to plug at: Hour: 10:30 a.m. Day: 16 Month: 12 Year: 19 91

Plugging proposal received from Rick Davis

(company name) Pipe Recovery Inc. (phone) 316-793-3922

were: 5 1/2" at 4407' w/125 sx cement, PBD 4110', Perfs at 4055-62'

1st plug sand back to 4005' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10' sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 150 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 5 p.m. Day: 16 Month: 12 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 4005' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 400 lbs. hulls, 10 sx gel, circulated on backside of 8 5/8" surface casing. Ran tubing to 1102' and pumped in 10 sx gel and 50 sx cement. 3rd plug pulled tubing to 490' and pumped in 140 sx cement. Cement did circulate. 4th plug layed down all tubing and filled 8 5/8" surface casing with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2121' of 5 1/2" casing. (If additional description is necessary, use BACK of this form.)

INVOICED

DATE 1-7-92

INV. NO. 34222

RECEIVED STATE CORPORATION COMMISSION
DEC 18 1991

CONSERVATION DIVISION WICHITA, KANSAS

Signed [Signature] (TECHNICIAN)

12-18-1991