

To: 1 120663
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5922

Operator: Patton Oil Company
Name & Address 672 W. 4th St.
Moisington, KS 67544

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Pipe Recovery Inc. License Number 30752

Address P.O. Box 7, Great Bend, KS 67530

Company to plug at: Hour: 1 p.m. Day: 16 Month: 12 Year: 19 91

Plugging proposal received from Rick Davis

(company name) Pipe Recovery Inc. (phone) 316-793-3922

were: 5 1/2" at 4513' w/150 sx cement, PBTB 4474', Perfs at 4442-52'

1st plug sand back to 4390' and dump 5 sx cement on top of sand through bailer,

2nd plug pump in 8 5/8" surface casing with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 150 sx cement.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 2:30 p.m. Day: 16 Month: 12 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 4390' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 350 lbs. hulls, 10 sx gel, 50 sx cement,

10 sx gel, 150 lbs. hulls, released 8 5/8" wiper plug and pumped 150 sx cement.

Pumping pressure 0-500 psi and shut in 50 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2227' of 5 1/2" casing.
(if additional description is necessary, use BACK of this form.)

INVOICED (if applicable) observe this plugging.

DATE 1-7-92

INV. NO. 34224

Signed Steve Middleton
(TECHNICIAN)

12-16 89R
API NUMBER 15- 047-21,260-0600

Irreg. Sec. SEC. 3, T 26 S, R 16 W/E

5560 feet from S section line

3020 feet from E section line
Southwest College

Lease Name _____ Well # B-12

County Edwards 146.73

Well Total Depth 4515 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 505

12-18-1991
RECEIVED
STATE CORPORATION COMMISSION

CONSERVATION DIVISION
WICHITA, KANSAS