

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER: 15-155-21,439-0000

SE-SW-SW SECTION 13 TOWNSHIP 26S RANGE 9W

OPERATOR LICENSE # 31191 330' FEET FROM S SECTION LINE

OPERATOR R & B Oil & Gas 4290' FEET FROM E SECTION LINE

NAME & P.O. Box 195

ADDRESS Attica, KS 67009-0195

LEASE NAME: Cole #2 78.78

COUNTY: Reno

WELL TOTAL DEPTH: 2,424'

PIPE: _____

SURFACE CASING: 8 5/8" at 225'

10/2

ABANDONED OIL WELL _____ GAS WELL _____ INPUT WELL _____ SWD _____ D&A X

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: Duke Drilling Co. Inc.

ADDRESS: 100 S. Main Suite #410 Wichita, KS 67202 LICENSE: # 5929

COMPANY TO PLUG AT: HOUR: 06:00 DAY: 2 MONTH: 10 YR: 1999

PLUGGING PROPOSAL RECEIVED FROM: John Armbruster

COMPANY NAME: Duke Drilling Co. Inc. PHONE: 316-267-1331

WERE: Fill hole with heavy mud and spot cement through the drill pipe. Spot 35 sxs. cement at 1400', spot 35 sxs. cement at 920', spot 35 sxs. cement at 275', spot 25 sxs. cement at 60', and fill rathole with 15 sxs. cement.

PLUGGING PROPOSAL RECEIVED BY: Steve Durrant

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART () NONE (XX)

COMPLETED: HOUR: 08:30 DAY: 2 MONTH: 10 YEAR: 1999

ACTUAL PLUGGING REPORT: Filled hole with heavy mud and spotted cement through the drill pipe. Spotted 35 sxs. cement at 1400', spotted 35 sxs. cement at 920', spotted 35 sxs. cement at 275', spotted 25 sxs. cement at 60', and filled rathole with 15 sxs. cement.

REMARKS: Used 60/40 posmix w/4% gel by Allied. Invoice # 2942

RECEIVED
KANSAS CORPORATION COMMISSION

I DID NOT OBSERVE THIS PLUGGING.

Michael R. Wilson
Michael R. Wilson

INVOICED

MAR 09 2000 3-9-00

DATE 3/13/00

CONSERVATION DIVISION
WICHITA, KS

INV. NO. 06/4/00

FORM CP-2/3
REV. 3/90

R