

15-155-20714-0000

2-010073

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
130 S. Market, Room 2078  
Wichita, Kansas 67202

API NUMBER: 12/29/80

W2 W2 SE, SECTION 36 TOWNSHIP 26 RANGE 8W

OPERATOR LICENSE # 6139 1320 FEET FROM S SECTION LINE  
2310 FEET FROM E SECTION LINE

OPERATOR JAY C BOYER  
NAME & BOX 511  
ADDRESS HAYS, KS 67601

LEASE NAME: FOULTON #2

COUNTY: RENO <sup>120.25</sup>

WELL TOTAL DEPTH: 3700' (3678')

PIPE: \_\_\_\_\_

SURFACE CASING: 8-5/8" @ 200'

ABANDONED OIL WELL  GAS WELL \_\_\_\_\_ INPUT WELL \_\_\_\_\_ SMD \_\_\_\_\_ D&A \_\_\_\_\_

OTHER WELL AS HEREINAFTER INDICATED: \_\_\_\_\_

PLUGGING CONTRACTOR: MIKE'S TESTING & SALVAGE INC  
ADDRESS: BOX 209, CHASE KS 67524 LICENSE: 31529

COMPANY TO PLUG AT: HOUR: 14:30 DAY: 14 MONTH: 3 YR: 1995

PLUGGING PROPOSAL RECEIVED FROM: JAY C BOYER

COMPANY NAME: JAY C BOYER PHONE: 913-625-6967

WERE: SAND TO 3570' & TOP W/4 SX CMT - SHOOT PIPE OFF -  
PULL PIPE TO 1250' & SPOT 35 SX CMT - PULL PIPE TO 700'  
& SPOT 35 SX CMT - PULL PIPE TO 250' & CIRC CMT TO  
SURF - PERFS @ 3623'-3624'  
4-1/2" CSG @ 3699'

PLUGGING PROPOSAL RECEIVED BY: DAVE WERTZ

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL ( \_\_\_\_\_ ) PART (  ) NONE ( \_\_\_\_\_ )

COMPLETED: HOUR: 18:15 DAY: 14 MONTH: 3 YEAR: 1995

ACTUAL PLUGGING REPORT:  
SANDED TO 3570' & TOPPED W/4 SX CMT - SHOT PIPE OFF @  
2924' - PULLED PIPE TO 1178' & SPOTTED 35 SX CMT -  
PULLED PIPE TO 569' & SPOTTED 35 SX CMT - PULLED PIPE  
TO 203' & CIRC 112 SX CMT TO SURF  
\*\*ACCORDING TO RIG OPERATOR, PIPE WAS SHOT OFF @  
3000' & THIS WAS USED TO CALCULATE PLUG DEPTHS.

REMARKS: USED 60/40 POZ W/4% GEL BY ALLIED #1787

I DID OBSERVE THIS PLUGGING.

**INVOICED**

Michael R. Wilson  
Michael R. Wilson (AGENT)

DATE: 3-28-95

FORM CP-2/3  
REV. 3/90

INV. NO. 42459

RECEIVED  
KANSAS CORPORATION COMMISSION  
MAR 27 1995  
CONSERVATION DIVISION  
WICHITA, KS