

2050209 *Rec'd 12-7-84*

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-155-20,895-0000

NW/4 SEC. 11, T 24 S, R 4 W

330 feet from N section line

660 feet from W section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5330

Lease Name E. Johnson Well # 1

Operator: Excalibur Prod. Co. Inc.

County Reed

Name & Address Box 278

Well Total Depth 3358 feet

M<sup>c</sup> Pherson, KS.

Conductor Pipe: Size        feet       

67460

Surface Casing: Size 12 3/4 feet 290

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated       

Plugging Contractor Helso Casing Pulling License Number       

Address Box 347 Chase, KS, 67524

Company to plug at: Hour: 9: AM Day: 3 Month: Dec Year: 19 84

Plugging proposal received from Norman Voth

(company name) Helso (phone)       

were: sand off bottom & dump 5 sx cement  
shot & pull pipe  
fill from 350 ft. to surface with  
Cement.

Plugging Proposal Received by Glenn Ward  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 1: PM Day: 3 Month: Dec Year: 19 84

ACTUAL PLUGGING REPORT open hole from 3358 to 3353.

sand back to 3300 ft. & dump 5 sx. Cement

shot & pulled 2191 ft. of 5 1/2 casing (58 Joints)

Pump thru swage 20 sx. Cel 6 sx. Halls & 200 sx

60/40 posmix with 3% CC.

Remarks: Allied Cementing  
(If additional description is necessary, use BACK of this form.)

**NOTICED** observe this plugging.

DATE 1-10-85

Signed Glenn Ward  
(TECHNICIAN)

INV. NO. 6357