

1030412

15-185-20900-00-01

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- Not Available

SW NW, SEC. 10, T 23 S, R 14 (W/EX)

4290 feet from S section line

4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8061

Lease Name Devore A Well # 1

Operator: Oil Producers

County Stafford

Name & Address P. O. Box 8647

Well Total Depth 4005 130.17 feet

Woodlawn, KS 67208

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8" feet 280

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 3:00 pm Day: 9 Month: May Year: 19 85

Plugging proposal received from Bob Brenneman

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" at 4004' PBTD 3990' Perfs at 3962-78'

1st plug sand back to 3910' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 1 sack hulls and 250 sx cement

Plugging Proposal Received by Steve Durrant  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 4:40 pm Day: 9 Month: May Year: 19 85

ACTUAL PLUGGING REPORT Casing parted at 216' and fell back in hole.

1st plug sanded back to 3910' and dumped 4 sx cement on top of sand through bailer

2nd plug pumped 1 sack hulls and 250 sx cement and shut in.

RECEIVED  
STATE CORPORATION COMMISSION

MAY 21 1985  
5-21-85

CONSERVATION DIVISION  
Wichita, Kansas

Maximum pressure 500 psi and shut in 0 psi

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Allied. No recovery.

(If additional description is necessary, use BACK of this form.)

INVOICED  
(If desired, observe this plugging.)

DATE 5-21-85

Signed Steve Durrant  
(TECHNICIAN)

INV. NO. 8219

5-9