

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-173-20215-00-00 Spot: CNENW  
Sec: 23 Twnshp & Dir: 29 S Rng & Dir: 4 W  
Feet: 660 frm N/S: N Feet: 1980 frm E/W: W  
Lease/Unit Name: BEARDMORE A Well Number: 1  
County: SEDGWICK Total Vertical Depth: 4350 feet

Operator License No.: 4549  
Operator Name: Anadarko Petroleum Corporatio  
Address: 1701 North Kansas Ave  
Liberal, KS 67905

Conductor Pipe: Size \_\_\_\_\_ feet:  
Surface Casing: Size 8.62 feet: 286  
Production: Size 4.5 feet: 4349 *141.38*

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/01/2000 12:00 PM  
Plug Co. License No.: 31151 Plug Co. Name: Sargent and Horton Plugging, Inc.  
Proposal Received from: Bob Atwood Company Name: Same  
OpRepPhoneNo: (316) 482-1000

Proposed Plugging Method: miru pmp 3sxs hulls, 10 sxs cmt displace w/9ppg mud pull free point shoot off 4 1/2' csg spot 35sxs cmt @ 750'-630' spot 35sxs cmt @ 340'-230' spot 10sxs cmt @ 30'-3' cut off and cap 85/8" csg 3" below gl. Rdmo. Restore location.

Plugging Proposal Received By: Dave Wertz WitnessType: Plugging Operations Partially Witnessed  
Date/Time Plugging Completed: 09/06/2000 12:00 PM

Actual Plugging Report:

Spotted 3 sx hull and 10 sx cement at 4312' through the 4 1/2" casing. Shot 4 1/2" casing off @ 2020', pulled to 330'. Spotted 35. Pulled 4 1/2" out of wellbore. Fluid @ 50'. Open ended 20 sx to surface. The top was not placed correctly as instructed by KCC Personnel.

RECEIVED  
KCC DISTRICT #2  
  
SEP 12 2000  
9-12-00  
WICHITA, KS

Remarks:  
Anhydrite Plug: No BottomPlug: \_\_\_\_\_ DakotaPlug: No  
Plugged through: CSG

I (did / did not) observe this plugging. \_\_\_\_\_

INVOICED Signed Dave Wertz  
(TECHNICIAN)

DATE 9/14/00  
INV. NO. 2001060676

*MB*