

15-155-20754-0000

2 090038

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION SWNWNW
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- D-C 3-81
SEC. 1, T 24 S, R. 4 W/E
feet from N/S section line
feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5808
Operator: W.R. Allam Jr.
Name & Address Hutchinson, Ks. 67504

Lease Name McElwain Estate Well # 2
County Reno
Well Total Depth 3363 109.30 feet
Conductor Pipe: Size 12 3/4" feet 267'
Surface Casing: Size feet

Abandoned Oil Well XX Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Gressel License Number 5823

Address P.O. Box 286, Burrton, Ks.

Company to plug at: Hour: 3:30 p.m. Day: 14 Month: 8 Year: 19 84

Plugging proposal received from
(company name) (phone)

were: sand back to 3300' 5 sacks cement bail to 316' bridge redi-mix 9 yds to surface

Plugging Proposal Received by (TECHNICIAN)

Plugging Operations attended by Agent?: All Part XX None

Operations Completed: Hour: Day: 14 Month: 8 Year: 19 84

ACTUAL PLUGGING REPORT The bottom of the hole was filled with sand to 3300' and 5 sacks of cement was spotted on top of sand through the bailer. The pipe was shot off and 2316' of 5 1/2" was recovered. The hole was bailed down to 316'; set a rock and wood bridge, redy mixed 9.5 yds to surface

Remarks: Haven Redi-Mix Ticket # 4894

(If additional description is necessary, use BACK of this form.)

observe this plugging.

8-20-84 RECEIVED STATE CORPORATION COMMISSION
AUG 20 1984 CONSERVATION DIVISION
Wichita, Kansas

INVOICED

DATE 8-21-84

Signed David Wertz (TECHNICIAN)

INV. NO. 3311

8-14 OCT 02 1984

FORM CP-2/3 Rev. 01-84