

2 100151

API NUMBER 15- 11-10-81

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

W/2 NW/4, SEC. 1, T 24 S, R 4 W/2

4950' ~~330~~ feet from S section line

41620' ~~660~~ feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5808

Lease Name McElwain Well # 1

Operator: W.R. Allam, Jr.

County Reno 108.75

Name & Address P.O. Box 2325

Well Total Depth 3346 feet

Hutchinson, KS 67504

Conductor Pipe: Size 10 3/4 feet 257

Surface Casing: Size 8 5/8" feet 563

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated 4 1/2" - 3340' (100 sks) open hole to 3355'

Plugging Contractor Gressel Well Service License Number 5823

Address Haysville, KS

Company to plug at: Hour: Day: 11 Month: 2 Year: 19 86

Plugging proposal received from Eddie Gressel

(company name) Burrton, KS (phone)

were: sand 50' inside pipe, and spot 5 sacks of cement on bottom - shoot and pull
2340 feet of pipe (4 1/2") - bridge at 400 feet - fill to top

Plugging Proposal Received by Dist # 2 W.R. (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: Day: 11 Month: 2 Year: 19 86

ACTUAL PLUGGING REPORT Sanded to 3280 feet and dump-bail 5 sacks of cement. Shot pipe
and pulled 2340 feet of 4 1/2". Pushed rubber plug to 400 feet inside 8 5/8".
Dumped 50 feet of sand. Filled to surface with redi-mix.

RECEIVED STATE CORPORATION COMMISSION

JUN 2 - 1986

CONSERVATION DIVISION
Wichita, Kansas

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED

Signed L.L. Sanders (TECHNICIAN)

DATE JUN 3 1986

INV NO. 14040