

824  
02-D10208

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-155-21437-00-00 Spot: CNESE  
Sec: 8 Twnshp & Dir: 23 S Rng & Dir: 8 W  
Feet: 1980 frm N/S: S Feet: 660 frm E/W: E  
Lease/Unit Name: LOUISE Well Number: 1-8  
County: RENO Total Vertical Depth: 3760 feet

Operator License No.: 5058  
Operator Name: Corsair Energy, LC  
Address: Sutton Place - STE 220  
Wichita, KS 67202

Conductor Pipe: Size \_\_\_\_\_ feet:  
Surface Casing: Size 8.625 feet: 206  
Production: Size \_\_\_\_\_ feet:

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/21/1999 11:30 PM  
Plug Co. License No.: 5142 Plug Co. Name: Sterling Drilling Company  
Proposal Received from: Vaughn Thompson Company Name: Sterling Drilling Co.

12220

OpRepPhoneNo: (316) 672-9508

Were: See actual plugging report

Plugging Proposal Received By: Dave Wertz, KCC WitnessType: Plugging Operations Were Not Witnessed  
Date/Time Plugging Completed: 08/22/1999 1:00 PM

Actual Plugging Report:

Filled hole w/heavy mud & spotted cem. thru drill pipe. 35 sxs. @ 1250'. 35 sxs. @ 750'. 35 sxs. @ 250', 25 sxs. @ 60'. Filled rat hole w/10sxs., mouse hole with 15 sxs. cement. Filled water well w/10 sxs. Cement. Used 60/40 posmix w/4% gel

Rec'd  
9-23-99

INVOICED  
DATE 9-24-99  
INV. NO. 2000060581

Remarks: United # 1662 SEE ACTUAL P/A REPORT IN DIST. 2 FILES

Anhydrite Plug: No BottomPlug: \_\_\_\_\_ DakotaPlug: No  
Plugged through: \_\_\_\_\_

I ~~(did)~~ did not observe this plugging.

Signed Michael Redmon  
(TECHNICIAN)

e/x